



Bryant Planning Commission Meeting

Boswell Municipal Complex - City Hall Court Room

210 SW 3rd Street

YouTube: <https://www.youtube.com/c/bryantarkansas>

Date: July 08, 2024 - **Time:** 9:00 AM

Call to Order

Approval of Minutes

1. Planning Commission Meeting Minutes 6/10/2024

Announcements

DRC Report

2. Walgreens - 5500 HWY 5 - Site Plan Revisions

Kimley-Horn - Requesting Approval for Site Plan Revisions - APPROVED

- [0880-PLN-01.pdf](#)
- [0880-LTR-01.pdf](#)

3. Big Dog Gym - 201 S Elm - Fencing

Requesting Approval for Fencing - APPROVED

- [0881-PLN-01.pdf](#)

4. Five Star Fireworks - Temporary Business License

Mark Bradford - Requesting Approval for Temporary Business License for Firework Sales at: 1.) 5407 HWY 5, 2.) 23395 I-30 - APPROVED, contingent upon proof of insurance, copy of state police license, and site inspection at each location.

- [0877-APP-01.pdf](#)
- [0878-APP-01.pdf](#)

5. Hurricane Lake Baptist Church - 2516 Springhill Road - New Awning

Requesting Site Plan Approval for New Awning - APPROVED

- [0885-PLN-01.jpg](#)

6. Arnold's Fireworks - Temporary Business License

Terry Harper - Requesting Approval for Temporary Business License for Firework Sales at: 1.) 604 S Reynolds Road, 2.) 2625 Springhill Road - APPROVED, Contingent upon Site Inspections

- [0883-APP-01.pdf](#)
- [0882-APP-01.pdf](#)

7. Miller and Hilltop Road - Two Lot Subdivision Plat

Hope Consulting - Requesting Final Plat Approval - RECOMMENDED APPROVAL, Contingent upon ROW Modification to plat, and BOA

8. Little Caesars - N. Reynolds and Brown Ln - Plat

Thomas Engineering - Requesting Approval for One Lot Commercial Subdivison Plat - RECOMMENDED APPROVAL

9. Alcoa 40 Park - Lacrosse Concessions Container

Adam Baker - Requesting Non-standard Building Approval for use of Modified Metal Shipping Container - RECOMMENDED APPROVAL

Old Business

New Business

10. Miller and Hilltop Road - Two Lot Subdivision Plat

Hope Consulting - Requesting Final Plat Approval

- [0884-PLN-01.pdf](#)

11. Little Caesar's - N Reynold's and Brown Ln

Thomas Engineering - Requesting Approval for One Lot Commercial Plat

- [0886-LTR-01.pdf](#)
- [0886-PLT-01.pdf](#)

12. Alcoa 40 Park - Lacrosse Concessions Container

Adam Baker - Requesting Non-standard Building Approval for use of Modified Metal Shipping Container

- [0887-PLN-01.pdf](#)

13. Planning Commission By-Law Revisions

Discussion and vote on approval of revisions to by-laws

Adjournments

CONSTRUCTION PLANS for

WALGREENS #10240 - BRYANT, AR

5500 HIGHWAY 5 N, BRYANT, AR 72022

CITY OF BRYANT, SALINE COUNTY, ARKANSAS

UTILITY AND GOVERNING AGENCIES
CONTACT LIST:

WATER COMPANY

CITY OF BRYANT PUBLIC WORKS
TIM FOURNIER
210 SW 3RD STREET
BRYANT, AR 72022
(501) 943-0469

SANITARY SEWER COMPANY

CITY OF BRYANT PUBLIC WORKS
TIM FOURNIER
210 SW 3RD STREET
BRYANT, AR 72022
(501) 943-0469

FIRE MARSHAL

CITY OF BRYANT FIRE DEPARTMENT
THOMAS HAMMOND
312 ROYA LANE
BRYANT, AR 72022
(501) 943-0397

EROSION CONTROL

CITY OF BRYANT ENGINEERING/CONSTRUCTION
SCOTT CHANDLER
210 SW 3RD STREET
BRYANT, AR 72022
(501) 943-0454

POWER COMPANY

ENTERGY
1(800) 368-3749

CABLE COMPANY

XFINITY
(800) 934-6489

DEPARTMENT OF TRANSPORTATION

ARKANSAS DEPARTMENT OF TRANSPORTATION
(501) 569-2000

PLANNING DEPARTMENT

CITY OF BRYANT COMMUNITY DEVELOPMENT
COLTON LEONARD
210 SW 3RD STREET
BRYANT, AR 72022
(501) 943-0301

ZONING DEPARTMENT


CITY OF BRYANT COMMUNITY DEVELOPMENT
COLTON LEONARD
210 SW 3RD STREET
BRYANT, AR 72022
(501) 943-0301

PHONE COMPANY

AT&T
(800) 288-2020

GAS COMPANY

CENTERPOINT ENERGY
(800) 992-7552



KIMLEY-HORN SHALL HAVE NO LIABILITY WHATSOEVER FOR ANY COSTS ARISING OUT OF THE CLIENT'S DECISION TO OBTAIN BIDS OR PROCEED WITH CONSTRUCTION BEFORE KIMLEY-HORN HAS ISSUED FINAL, FULLY-APPROVED PLANS AND SPECIFICATIONS. THE CLIENT ACKNOWLEDGES THAT ALL PRELIMINARY PLANS ARE SUBJECT TO SUBSTANTIAL REVISION UNTIL PLANS ARE FULLY APPROVED AND ALL PERMITS OBTAINED.

NOTICE TO CONTRACTOR:

ALL WORK AND MATERIALS SHALL CONFORM TO THE MOST CURRENT STANDARDS AND SPECIFICATIONS AS PROVIDED IN THE:

CITY OF BRYANT ZONING CODE AND ORDINANCES
ARDOT STANDARDS SPECIFICATIONS FOR ROADS AND STRUCTURES
OR THE MORE RESTRICTIVE OF ANY STANDARDS THAT CONFLICT.

SHEET INDEX	
Sheet Number	Sheet Title
C001	COVER SHEET
C002	GENERAL NOTES
C101	TOPOGRAPHICAL SURVEY
C105	DEMOLITION PLAN
C201	EROSION CONTROL PLAN - PHASE 1
C202	EROSION CONTROL DETAILS
C301	SITE PLAN
C401	GRADING AND DRAINAGE PLAN
C901	SITE DETAILS

PROJECT OWNER AND CONSULTANT INFORMATION		
<p>DEVELOPER:</p> <p style="font-size: x-small;">WALGREENS COMPANY 106 WILMOT ROAD MS 1620 DEERFIELD, IL 60015 PHONE (508) 265-9281</p> <p style="font-size: x-small;">CONTACT: BENJAMIN LANGLOIS</p>	<p>ENGINEER:</p> <p style="font-size: x-small;">KIMLEY-HORN AND ASSOCIATES, INC. 805 S WALTON BLVD SUITE #520 BENTONVILLE, AR 72712 (479) 388-1015 TEL</p> <p style="font-size: x-small;">CONTACT: BRIAN M. COX, P.E. (AR)</p>	<p>SURVEYOR:</p> <p style="font-size: x-small;">CORNERSTONE LAND SURVEYING 25 SKY DRIVE GREENBRIER, AR 72058 PHONE (501) 679-1318</p> <p style="font-size: x-small;">CONTACT: JARED PAVATT</p>

GEOMETRIC CONTROL

HORIZONTAL DATUM:
NAD 83 (2011)

VERTICAL DATUM:
NAVD 88

DRAWING UNITS:
U.S. SURVEY FEET



No.	REVISIONS	DATE	BY

Kimley >>> Horn

© 2024 KIMLEY-HORN AND ASSOCIATES, INC.
200 SOUTH TRYON ST. SUITE 200, CHARLOTTE, NC 28202
PHONE: 704-338-5131
WWW.KIMLEY-HORN.COM
FIRM COA NO. 51

STATE OF ARKANSAS
LICENSED PROFESSIONAL ENGINEER
No. 21699

NOT FOR CONSTRUCTION

KH PROJECT	014677008	DATE	05/28/2024	SCALE	AS SHOWN	DESIGNED BY	TTP	DRAWN BY	TTP	CHECKED BY	BMC
------------	-----------	------	------------	-------	----------	-------------	-----	----------	-----	------------	-----

COVER SHEET

WALGREENS #10240 -
BRYANT, ARKANSAS
PREPARED FOR
WALGREENS COMPANY
BRYANT, AR

SHEET NUMBER
C001

Plotted By: Pouch, Title: Sheet Set: Walgreens #10240 - Bryant, Arkansas Layout: C001 - COVER SHEET, May 24, 2024, 01:29:30pm, K:\CHL - PRJ\018197\HSE\KH PAU\041 - Walgreens Eminent Domain\036 Bryant, AR (R\10240)\05 - TIER 202 - DWG\PlanSheets\C001 - COVER SHEET.dwg

General Notes for Walgreens #10240 - Bryant, Arkansas. The document lists 53 numbered items detailing construction requirements for erosion control, stormwater management, and site preparation. It covers topics like material specifications, site grading, utility protection, and safety protocols. The notes are organized into sections such as 'Demolition', 'Grading', 'Pond Notes', and 'Water and Wastewater'.

Project Information and Revisions Table. Includes fields for Project Name (Walgreens #10240 - Bryant, Arkansas), Date (05/28/2024), Scale (AS SHOWN), and a Revisions column with 11 empty rows for tracking changes. The table also contains a 'Not for Construction' stamp and a signature block for a Licensed Professional Engineer.

Header table with columns: No., Revisions, Date, By.

Table with 4 columns: No., Revisions, Date, By.

Table with 4 columns: No., Revisions, Date, By.

Table with 4 columns: No., Revisions, Date, By.



Stamp: NOT FOR CONSTRUCTION. Includes fields for Project, Date, Scale, Design, Draw, Check, and other project details.


General Notes section for Walgreens #10240 - Bryant, Arkansas. Prepared for Walgreens Company. Includes the company logo and contact information.















This document, together with the notes and details associated therewith, is an instrument of service. It is intended to be used as an instrument of service. It shall be without liability to Kimley-Horn and Associates, Inc.


Plotted By: Pouch, Title Sheet Set: Walgreens #10240 - Bryant, Arkansas Topographical Survey, May 24, 2024 01:11:47pm K:\CHL_FRJ018197_HSF&H_PA041_Walgreens Eminent Domain\036 Bryant, AR #10240\036_TIER 202 - DWG\PlanSheets\C101 - EXST COND PLAN.dwg

CORNERSTONE
 SURVEYING & MAPPING
 1170 BOX 1074
 GREENBERG, AR 72688
 PHONE (501) 679-1318
 survey@cornerstone.net



LEGEND


-  POWER POLE (OVER-HEAD ELECTRIC)
-  GUY WIRE ANCHOR
-  LIGHT POLE
-  WARNING OR INFO SIGN
-  STORM DRAIN COVER
-  WATER UTILITY BOX
-  UTILITY VALVE
-  FIRE HYDRANT
-  TELEPHONE PEDESTAL
-  SANITARY SEWER MANHOLE
-  UTILITY AS NOTED
-  GAS SERVICE



DRAWING INFORMATION		PROJECT TITLE	
FIELD TECH	A.P.	WALGREENS - BRYANT TOPOGRAPHICAL SURVEY LITTLE ROCK, ARKANSAS	
DRAWN BY	A.P.		
DRAWING DATE	10/19/23		
DRAWING SCALE	1"=20'		
SHEET NUMBER		PROJECT NUMBER	
G-1		WALGREENS - BRYANT	

05/28/2024 KHA PROJECT 01487708
TOPOGRAPHICAL SURVEY C101
 FOR REFERENCE ONLY

Plotted By: Pouch, Title Sheet: Walgreens #10240 - Bryant, Arkansas Layout: C105 DEMO, May 24, 2024, 01:12:50pm, K:\CHL\PE\J018197_HSF&H_PAU041\Walgreens Eminent Domain\038 Bryant_AR (#10240)\05_TIER 202 - DWG\PlanSheets\C105 - DEMO.dwg



NOTE TO CONTRACTOR

CONTRACTOR SHALL TAKE EXTREME CARE WHEN WORKING AROUND EXISTING UTILITIES. CONTRACTOR SHALL REPAIR ANY DAMAGED FEATURES/UTILITIES TO THAT OF EXISTING OR BETTER CONDITION.

CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL REPAIRS TO ANY DAMAGED ROADWAYS, CURB AND GUTTER, ASPHALT, ETC.

CONTRACTOR SHALL COMPLETELY REMOVE ALL FEATURES WITHIN THE LIMITS OF CONSTRUCTION / OVERALL PROJECT BOUNDARY IN ORDER TO CONSTRUCT PROPOSED IMPROVEMENTS AS SHOWN IN THESE PLANS.

ALERT TO CONTRACTOR

PRIOR TO THE CONSTRUCTION OF OR CONNECTION TO ANY STORM DRAIN, SANITARY SEWER, WATER MAIN OR ANY OF THE DRY UTILITIES, THE CONTRACTOR SHALL EXCAVATE, VERIFY AND CALCULATE ALL POINTS OF CONNECTION AND ALL UTILITY CROSSINGS AND INFORM CIVIL ENGINEERING CONSULTANT AND THE OWNER/DEVELOPER OF ANY CONFLICT OR REQUIRED DEVIATIONS FROM THE PLAN. NOTIFICATION SHALL BE MADE A MINIMUM OF 48 HOURS PRIOR TO CONSTRUCTION. CIVIL ENGINEERING CONSULTANT AND ITS CLIENTS SHALL BE HELD HARMLESS IN THE EVENT THAT THE CONTRACTOR FAILS TO MAKE SUCH NOTIFICATION.

TREE PROTECTION NOTES

- THE CONTRACTOR SHALL PROTECT ALL TREES AND SHRUBS OUTSIDE OF CUT/FILL LINES, IN ADDITION TO THOSE THAT RECEIVE TREE/SHRUB PROTECTION BARRIERS. THE CONTRACTOR IS ALSO REQUESTED TO SAVE ALL OTHER EXISTING TREES AND SHRUBS WHERE POSSIBLE.
- WHEN ROOT PRUNING IS NECESSARY, CUT ROOTS CLEANLY USING A DISC TRENCHER AND IMMEDIATELY COVER ALL ROOT CUT SURFACES LARGER THAN TWO INCHES IN DIAMETER WITH TREE WOUND DRESSING. USE PLYWOOD FORMS WHEN TREE ROOTS ARE ADJACENT TO PROPOSED CURB & GUTTER OR SIDEWALK.
- NO SOIL DISTURBANCE OR COMPACTION, CONSTRUCTION MATERIALS, TRAFFIC, BURIAL PITS, TRENCHING OR OTHER LAND DISTURBING ACTIVITY ALLOWED IN THE TREE PROTECTION ZONE. TREE BARRICADES MUST BE INSTALLED BEFORE ANY DEMOLITION, GRADING OR CONSTRUCTION BEGINS, AND NOT REMOVED UNTIL FINAL INSPECTION.
- NO GRUBBING WITHIN TREE PROTECTION ZONE. LEAVE SOIL AND LEAF LITTER UNDISTURBED. SUPPLEMENT WITH 1-2 INCHES OF MULCH. RE-SEED WITH GRASS ONLY IN DISTURBED/GRADED AREAS.
- TREE BARRICADES MUST BE INSTALLED BEFORE ANY DEMOLITION, CLEARING, GRADING OR CONSTRUCTION BEGINS AND IS NOT TO BE REMOVED UNTIL AFTER CONSTRUCTION.

CAUTION!
CONTRACTOR IS TO VERIFY PRESENCE AND EXACT LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.

DEMOLITION LEGEND

- FULL DEPTH PAVEMENT REMOVAL - CLEAN SAWCUT EDGE
- EXISTING LINEAR ITEM TO BE REMOVED
- LIMITS OF DISTURBANCE (LOD)

DISTURBED AREA

TOTAL - ± 0.14 - ACRE

DISCLAIMER: AERIAL IMAGERY IS TAKEN FROM NEARMAP DATED JUNE 30, 2023, AND IS SHOWN FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING IMPROVEMENTS PRIOR TO BEGINNING CONSTRUCTION.

PROPERTY LINE AND EXISTING RIGHT-OF-WAY IS AN APPROXIMATION AND IS NOT TO BE USED AS A SITE REFERENCE POINT.

GRAPHIC SCALE IN FEET: 0, 10, 20, 40

811
Know what's below.
Call before you dig.

	DATE
	REVISIONS
	No.

© 2024 KIMLEY-HORN AND ASSOCIATES, INC.
200 SOUTH TRYON ST. SUITE 200, CHARLOTTE, NC 28202
WWW.KIMLEY-HORN.COM
FIRM COA NO. 51

NOT FOR CONSTRUCTION

KH PROJECT 014677008	DATE 05/28/2024	SCALE AS SHOWN	DESIGNED BY TTP
			CHECKED BY BMC


DEMOLITION PLAN

WALGREENS #10240 - BRYANT, ARKANSAS
PREPARED FOR
WALGREENS COMPANY
BRYANT, AR

SHEET NUMBER
C105

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

Plotted By: Pouch, Title Sheet: Walgreens #10240 - Bryant, Arkansas Layout: C201 - ESCP PH1 - May 24, 2024, 01:13:20pm, K:\CHL - PRJ\018197_HSF&H PA041 Walgreens Eminent Domain\038 Bryant_AR (#10240)\05_TIER 2\02 - DWG\PlanSheets\C201 - ESCP PH1.dwg



PROPOSED ESCP LEGEND	
	LOD - LIMITS OF DISTURBANCE
	SF - TEMPORARY SILT FENCE
	CW - 12" COIR WATTLE/FILTREX FILTER SOXX CONSTRUCTION FENCE
	CF - CONSTRUCTION FENCE
	SA - SLOPE ARROW / FLOW ARROW
	IP - INLET PROTECTION
	PROPOSED CURB & GUTTER

- NOTES TO CONTRACTOR**
- REFER TO GENERAL NOTES SHEET FOR EROSION CONTROL NOTES.
 - OWNER CREEK - FOURCHE CREEK IS THE RECEIVING WATER BODY OF STORMWATER DISCHARGE FROM THIS SITE.
 - ANY OFF-SITE BORROW AND WASTE REQUIRED FOR THIS PROJECT MUST COME FROM A SITE WITH AN APPROVED EROSION CONTROL PLAN, A SITE REGULATED UNDER THE MINING ACT OF 1971, OR A LANDFILL REGULATED BY THE DIVISION OF SOLID WASTE MANAGEMENT. TRASH/DEBRIS FROM DEMOLITION ACTIVITIES OR GENERATED BY ANY ACTIVITIES ON SITE MUST BE DISPOSED OF AT A FACILITY REGULATED BY THE DIVISION OF SOLID WASTE MANAGEMENT OR PER DIVISION OF SOLID WASTE MANAGEMENT OR DIVISION OF WATER RESOURCES RULES AND REGULATIONS.
 - STOCKPILES SHOULD NOT BE LOCATED WITHIN 50 FEET OF ANY STORM DRAIN, BASIN, OR STREAM UNLESS NO ALTERNATIVE IS FEASIBLE.
 - EFFECTIVE OCTOBER 1, 2010, PERSONS RESPONSIBLE FOR LAND DISTURBING ACTIVITIES MUST INSPECT THE SEDIMENT AND EROSION CONTROL MEASURES ON A PROJECT AFTER EACH PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEING FOLLOWED. SELF INSPECTION REPORTS ARE REQUIRED. A SAMPLE SELF-INSPECTION REPORT, AS WELL AS DETAILS OF THE SELF-INSPECTION PROGRAM, CAN BE FOUND ON THE LAND QUALITY WEB SITE.

DISTURBED AREA
TOTAL - ± 0.14 - ACRE

NO.	REVISIONS	DATE	BY

Kimley

© 2024 KIMLEY-HORN AND ASSOCIATES, INC.
200 SOUTH TRYON ST. SUITE 200, CHARLOTTE, NC 28202
PHONE: 704-333-5131
WWW.KIMLEY-HORN.COM
FIRM CO. NO. 51

STATE OF ARKANSAS
LICENSED PROFESSIONAL ENGINEER
No. 21699
BRYANT, AR

NOT FOR CONSTRUCTION


KH PROJECT	014677008
DATE	05/28/2024
SCALE	AS SHOWN
DESIGNED BY	TTP
DRAWN BY	TTP
CHECKED BY	BMC

EROSION CONTROL PLAN - PHASE 1

WALGREENS #10240 - BRYANT, ARKANSAS
PREPARED FOR
WALGREENS COMPANY
BRYANT, AR

DISCLAIMER: AERIAL IMAGERY IS TAKEN FROM NEARMAP DATED JUNE 30, 2023, AND IS SHOWN FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING IMPROVEMENTS PRIOR TO BEGINNING CONSTRUCTION.


PROPERTY LINE AND EXISTING RIGHT-OF-WAY IS AN APPROXIMATION AND IS NOT TO BE USED AS A SITE REFERENCE POINT.



SHEET NUMBER
C201

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

Plotted By: Pouch, Title Sheet: Walgreens #10240 - Bryant, Arkansas Layout: C301 - SITE PLAN, May 24, 2024, 01:13:59pm, K:\CHL_P\018197_HSF&H PA041 Walkgreens Emment Domain\038 Bryant_AR (10240)008_TIER 202 - DWG\Plans\Sheets\C301 - SITE PLAN.dwg



SITE DEVELOPMENT PLAN NOTES

- SEE "GENERAL NOTES" SHEET FOR SITE GENERAL CONSTRUCTION NOTES, PAVING, STRIPING, GRADING, AND ZONING NOTES.
- SEE "TOPOGRAPHICAL SURVEY" FOR COMPLETE BOUNDARY DESCRIPTION, ADJOINING PROPERTIES, ZONING AND USE.
- SEE "SITE DETAILS" SHEETS FOR DETAILS REFERENCED ON THE SITE PLANS.
- ALL DIMENSIONS SHOWN ARE MEASURED FROM THE FACE OF CURB TO FACE OF CURB, UNLESS OTHERWISE NOTED. DIMENSIONS LABELED "EOP" ARE MEASURED FROM LIP OF GUTTER TO LIP OF GUTTER.
- DIMENSIONS TO THE BUILDING ARE MEASURED TO THE EXTERIOR OF THE FOUNDATION WALL UNLESS OTHERWISE SHOWN.
- BEARINGS, DIMENSIONS AND EASEMENTS ARE SHOWN FOR REFERENCE. REFER TO RECORDED PLATS AND SURVEYS FOR ADDITIONAL PROPERTY INFORMATION.

SITE DATA TABLE

DEVELOPMENT DATA:	
TAX PARCEL ID	840-12074-002
LAND USE	COMMERCIAL
TOTAL SITE AREA	2.56 ACRES
TOTAL DISTURBED AREA	0.14 ACRES
ZONING DATA:	
FEMA FLOOD PANEL	05125C0380E
ZONING DISTRICT:	C-2
MIN. LOT SIZE:	20,000 SF
MIN. LOT WIDTH:	100 FT
MAX. HEIGHT:	4 STORIES
SETBACKS:	
FRONT YARD	15 FT
SIDE YARD INTERIOR	15 FT
SIDE YARD EXTERIOR	15 FT
REAR YARD	25 FT

SITE DATA TABLE

PARKING	
PARKING PROVIDED:	69 SPACES
STANDARD PARKING:	65 SPACES
ADA PARKING / VAN:	3 / 1 SPACES
PARKING REQUIRED:	50 SPACES
STANDARD PARKING:	48 SPACES
ADA PARKING / VAN:	1 / 1 SPACES

SITE PLAN KEY NOTES

- SEE "GENERAL NOTES" SHEETS FOR SITE GENERAL NOTES.
- SEE "SITE DETAIL" SHEETS FOR DETAILS REFERENCED ON THE SITE PLANS.

SITE IMPROVEMENTS

- (A) STANDARD 18" CURB AND GUTTER (SEE SITE DETAIL SHEET)
- (B) PROPOSED 2" CURB END TRANSITION - NOT USED
- (C) PROPOSED ACCESSIBLE ROUTE
- (D) 4" THICKNESS CONCRETE SIDEWALK PER DETAIL. WIDTH PER PLAN. 2% MAX. CROSS SLOPE, 5% MAX LONGITUDINAL SLOPE.
- (E) PROPOSED SITE LIGHT POLE AND CONDUIT TO BE DESIGNED/COORDINATED BY OTHERS
- (F) EXISTING ACCESSIBLE RAMP
- (G) 5' CURB CUT (SEE SITE DETAIL SHEET)

PAVEMENT MARKINGS

- (M1) PAINTED DIRECTIONAL ARROW PAVEMENT MARKING - WHITE
- (M2) SWSL 4" - SINGLE WHITE SOLID LINE - 4" WIDE

PROPOSED PROPERTY LEGEND

— Ex-ROW —	— EXISTING RIGHT-OF-WAY
— BSL —	— EXISTING BUILDING SETBACK
— UE —	— EXISTING UTILITY EASEMENT
— LOD —	— PROPOSED LIMITS OF DISTURBANCE

PROPOSED LANDSCAPE

BERMUDA GRASS SOD	1,578 SQ FT	
-------------------	-------------	--


MISC.	QTY	BOTANICAL/COMMON NAME	SPECIFICATIONS
SOD	1578 SF	BERMUDA GRASS	ROLLED TIGHT, 100% WEED/INSECT/DISEASE FREE

- LANDSCAPE NOTES:**
- ALL LANDSCAPED AREAS ARE TO RECEIVE A MINIMUM OF 3" OF TOPSOIL. DO NOT MOUND MULCH AGAINST ROOT FLARES.
 - ALL PLANT MATERIAL SHALL BE HEALTHY, VIGOROUS, AND FREE OF PESTS AND DISEASE.
 - ALL MATERIALS ARE SUBJECT TO THE APPROVAL OF THE LANDSCAPE ARCHITECT BEFORE, DURING, AND AFTER INSTALLATION.
 - ALL TREES MUST BE GUYED OR STAKED AS SHOWN IN THE DETAILS.
 - ALL PLANTING AREAS SHALL BE COMPLETELY MULCHED AS SPECIFIED.
 - ANY DISTURBED GRASS AREA IS TO BE REPLANTED. ALL SLOPES 3:1 OR GREATER SHALL BE SEEDED WITH SLOPE MASTER NO-MOW MIX OR OWNER APPROVED EQUAL.
 - PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES AND SHALL AVOID DAMAGE TO ALL UTILITIES DURING THE COURSE OF THE WORK. LOCATIONS OF EXISTING BURIED UTILITY LINES SHOWN ON THE PLANS ARE BASED UPON BEST AVAILABLE INFORMATION AND ARE TO BE CONSIDERED APPROXIMATE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR 1) TO VERIFY THE LOCATIONS OF UTILITY LINES AND ADJACENT TO THE WORK AREA 2) TO PROTECT OF ALL UTILITY LINES DURING THE CONSTRUCTION PERIOD 3) TO REPAIR ANY AND ALL DAMAGE TO UTILITIES, STRUCTURES, SITE APPURTENANCES, ETC. WHICH OCCURS AS A RESULT OF THE CONSTRUCTION.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL QUANTITIES SHOWN ON THESE PLANS BEFORE PRICING THE WORK.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR DELIVERY SCHEDULE AND PROTECTION BETWEEN DELIVERY AND PLANTING TO MAINTAIN HEALTHY PLANT CONDITIONS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR FULLY MAINTAINING (INCLUDING BUT NOT LIMITED TO: WATERING, SPRAYING, MULCHING, FERTILIZING, ETC.) ALL OF THE PLANT MATERIALS AND LAWN FOR THE WARRANTY PERIOD.
 - ANY PLANT MATERIAL WHICH IS DISEASED, DISTRESSED, DEAD, OR REJECTED (PRIOR TO SUBSTANTIAL COMPLETION) SHALL BE PROMPTLY REMOVED FROM THE SITE AND REPLACED WITH MATERIAL OF THE SAME SPECIES, QUANTITY, AND SIZE AND MEETING ALL PLANT LIST SPECIFICATIONS.
 - THE CONTRACTOR SHALL COMPLETELY GUARANTEE ALL PLANT MATERIAL FOR WARRANTY PERIOD. THE CONTRACTOR SHALL PROMPTLY MAKE ALL REPLACEMENTS DURING THE NORMAL PLANTING SEASON.
 - STANDARDS SET FORTH IN "AMERICAN STANDARD FOR NURSERY STOCK" REPRESENT GUIDELINE SPECIFICATIONS ONLY AND SHALL CONSTITUTE MINIMUM QUALITY REQUIREMENTS FOR PLANT MATERIAL.
 - ALL LANDSCAPING SHALL BE INSTALLED ACCORDING TO SOUND NURSERY PRACTICES, AND SHALL BE STATE STANDARD OR BETTER.
 - ALL INVASIVE / EXOTIC SPECIES AND PROHIBITED TREE SPECIES SHALL BE REMOVED FROM SITE, INCLUDING ROOT BALLS TO THE EXTENT POSSIBLE WITH NO DAMAGE TO ADJACENT EXISTING TREES.
 - IF IRRIGATION IS REQUIRED, CONTRACTOR TO DESIGN BUILD SYSTEM AND VERIFY ALL PRODUCTS WITH LANDSCAPE ARCHITECT.
 - TREE SUPPORT MATERIALS ARE TO BE REMOVED FROM EACH TREE ONCE IT IS "ESTABLISHED" (AS APPROVED BY THE LANDSCAPE ARCHITECT).
 - CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING ALL UTILITIES ARE ADEQUATELY SCREENED WITH THE REQUIRED PLANTING MATERIAL AND VERIFY PLANT SPECIES WITH LANDSCAPE ARCHITECT.
 - ALL PLANT SPECIFICATIONS IN THE PLANT SCHEDULE SHALL BE CONSIDERED THE MINIMUM ALLOWABLE SPECIFICATIONS. CONTRACTOR SHALL PROCURE PLANT MATERIALS AND UPSIZE AS NECESSARY TO MEET THE MOST STRINGENT SPECIFICATION.

- NOTES:**
- ESTABLISH SOD IN ALL DISTURBED AREAS. SEE SPECIFICATIONS FOR MORE INFORMATION.
 - ALL AREAS WITH PROPOSED LANDSCAPE MATERIAL SHALL RECEIVE A MINIMUM THREE (3) INCHES OF SHREDDED HARDWOOD MULCH. SEE LANDSCAPE PLAN FOR MULCH BOUNDARY LINES. SEE LANDSCAPE DETAILS FOR TYPICAL MULCH AREA DIMENSIONS.

DISCLAIMER: AERIAL IMAGERY IS TAKEN FROM NEARMAP DATED JUNE 30, 2023, AND IS SHOWN FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING IMPROVEMENTS PRIOR TO BEGINNING CONSTRUCTION.

PROPERTY LINE AND EXISTING RIGHT-OF-WAY IS AN APPROXIMATION AND IS NOT TO BE USED AS A SITE REFERENCE POINT.



NO.	REVISIONS	DATE	BY

Kimley & Horn
 © 2024 KIMLEY-HORN AND ASSOCIATES, INC.
 200 SOUTH TRYON ST. SUITE 200, CHARLOTTE, NC 28202
 PHONE: 704-333-5131
 WWW.KIMLEY-HORN.COM
 FIRM CO. NO. 51



NOT FOR CONSTRUCTION


KH PROJECT	014677008	DATE	05/28/2024	SCALE	AS SHOWN	DESIGNED BY	TTP	DRAWN BY	TTP	CHECKED BY	BMC
------------	-----------	------	------------	-------	----------	-------------	-----	----------	-----	------------	-----

SITE PLAN

WALGREENS #10240 - BRYANT, ARKANSAS
 PREPARED FOR
WALGREENS COMPANY
 BRYANT, AR

SHEET NUMBER
C301

Plotted By:Pouch, Title Sheet:Walgreens #10240 - Bryant, Arkansas Layout:GRDG DRNG, May 24, 2024, 01:14:29pm, K:\C\H\PRJ\018197\HFKH\PA041\Walgreens Eminent Domain\036 Bryant_AR (10240)\05_TIER.202 - DWG\PlanSheets\C401 - GRDG DRNG OA.dwg



GRADING NOTES:

- REFER TO THE GENERAL NOTES SHEET FOR NOTES PERTAINING TO PAVING, GRADING, ACCESSIBILITY, AND STORM DRAINAGE.
- EXISTING AND PROPOSED GRADE CONTOURS INTERVALS SHOWN AT 1 FOOT.
- ALL SPOT ELEVATIONS WITH FC: REPRESENTS THE FACE OF CURB AT THE GUTTER LINE. (ADD 0.50' FOR TOP OF CURB.)
- ALL SPOT ELEVATIONS WITH TC: REPRESENTS THE TOP OF CURB ELEVATION. (SUBTRACT 0.50' FOR PAVEMENT OR ELEVATION OF GUTTER AT CURB LINE.)
- RIM: ELEVATIONS OF CATCH BASINS (CURB INLETS) EQUALS THE FLOW LINE OF THE GUTTER PAN. RIM ELEVATIONS OF DROP INLETS, MANHOLES, AND CLEANOUTS EQUALS THE CENTER OF GRATE OR LID ELEVATION.
- ALL STRUCTURES SHALL BE ADJUSTED AS NECESSARY TO BE FLUSH WITH FINAL PAVEMENT AT FACE OF CURB.
- MANHOLES WITHIN NON PAVED AREAS SHALL BE 6" ABOVE ADJACENT GRADES, UNLESS OTHERWISE SHOWN.
- CONTRACTOR SHALL PROVIDE SMOOTH TRANSITION BETWEEN PROPOSED PAVEMENT AND EXISTING PAVEMENT AND STORM STRUCTURES.
- DURING CONSTRUCTION AND AFTER FINAL GRADING, NO SURFACE WATER RUNOFF MAY BE DIRECTED TO ADJACENT PROPERTIES, AND ALL SURFACE WATER RUNOFF MUST BE ROUTED TO APPROVED DRAINAGE FACILITIES OR BE RETAINED ON SITE. ALL RUNOFF FROM THE SITE, BOTH DURING AND AFTER CONSTRUCTION, MUST BE FREE OF POLLUTANTS, INCLUDING SEDIMENT, PRIOR TO DISCHARGE.


ADA COMPLIANCE:

- CURB RAMP ALONG PUBLIC STREETS AND IN THE PUBLIC RIGHT-OF-WAY SHALL BE CONSTRUCTED BASED ON THE CITY STANDARD CONSTRUCTION DETAILS AND SPECIFICATIONS.
- PRIVATE CURB RAMP ON THE SITE (I.E. OUTSIDE PUBLIC STREET RIGHT-OF-WAY) SHALL CONFORM TO THE ADA STANDARDS FOR ACCESSIBLE DESIGN AND SHALL HAVE A DETECTABLE WARNING SURFACE THAT IS FULL WIDTH OF THE CURB RAMP, NOT INCLUDING FLARES.
- ALL ACCESSIBLE ROUTES, GENERAL SITE AND BUILDING ELEMENTS, RAMPS, CURB RAMPS, STRIPIN, AND PAVEMENT MARKINGS SHALL CONFORM TO ADA STANDARDS FOR ACCESSIBLE DESIGN, LATEST EDITION.
- BEFORE PLACING PAVEMENT, CONTRACTOR SHALL VERIFY THAT SUITABLE ACCESSIBLE PEDESTRIAN ROUTES (PER ADA AND FHA) EXIST TO AND FROM EVERY DOOR AND ALONG SIDEWALKS, ACCESSIBLE PARKING SPACES, ACCESS AISLES, AND ACCESSIBLE ROUTES. IN NO CASE SHALL AN ACCESSIBLE RAMP SLOPE EXCEED 1 VERTICAL TO 12 HORIZONTAL. IN NO CASE SHALL SIDEWALK CROSS SLOPE EXCEED 2.0 PERCENT. IN NO CASE SHALL LONGITUDINAL SIDEWALK SLOPE EXCEED 5.0 PERCENT. ACCESSIBLE PARKING SPACES AND ACCESS AISLES SHALL NOT EXCEED 2.0 PERCENT SLOPE IN ANY DIRECTION.
- CONTRACTOR SHALL TAKE FIELD SLOPE MEASUREMENTS ON FINISHED SUBGRADE AND FORM BOARDS PRIOR TO PLACING PAVEMENT TO VERIFY THAT ACCESSIBLE SLOPE REQUIREMENTS ARE PROVIDED. CONTRACTOR SHALL CONTACT ENGINEER PRIOR TO PAVING IF ANY EXCESSIVE SLOPES ARE ENCOUNTERED. NO CONTRACTOR CHANGE ORDERS WILL BE ACCEPTED FOR ADA COMPLIANCE ISSUES.

ALERT TO CONTRACTOR: CONFIRM WITH GEOTECH REPORT

THE PRESENCE OF GROUNDWATER SHOULD BE ANTICIPATED ON THIS PROJECT. CONTRACTOR'S BID SHALL INCLUDE CONSIDERATION FOR THIS ISSUE. WHEN PERFORMING GRADING OPERATIONS DURING PERIODS OF WET WEATHER, PROVIDE ADEQUATE DEWATERING, DRAINAGE AND OPERATIONS WATER MANAGEMENT TO CONTROL MOISTURE OF SOILS. REFER TO MASTER SITE SPECIFICATIONS.

PROPOSED TOPOGRAPHIC LEGEND



NOT FOR CONSTRUCTION


KH PROJECT	014677008	DATE	05/28/2024	SCALE	AS SHOWN	DESIGNED BY	TTP	DRAWN BY	TTP	CHECKED BY	BMC
------------	-----------	------	------------	-------	----------	-------------	-----	----------	-----	------------	-----

GRADING AND DRAINAGE PLAN

WALGREENS #10240 - BRYANT, ARKANSAS
PREPARED FOR
WALGREENS COMPANY
BRYANT, AR

DISCLAIMER: AERIAL IMAGERY IS TAKEN FROM NEARMAP DATED JUNE 30, 2023, AND IS SHOWN FOR GENERAL INFORMATION ONLY. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING IMPROVEMENTS PRIOR TO BEGINNING CONSTRUCTION.

PROPERTY LINE AND EXISTING RIGHT-OF-WAY IS AN APPROXIMATION AND IS NOT TO BE USED AS A SITE REFERENCE POINT.





SHEET NUMBER
C401

NO.	REVISIONS	DATE	BY


This document, together with the reports and designs presented herein, is intended solely for the specific purpose and client for which it was prepared. Review of and reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

Plotted By: Pouch, Title: Sheet Set: Walgreens #10240 - Bryant, Arkansas Layout: SITE-DET, May 24, 2024, 01:14:49pm, K:\CHL_P\PRJ018197_HSF&H\PA041_Walgreens Eminent Domain\035 Bryant_AR (10240)\05_TIER 202 - DWG\PlanSheets\001 - SITE-DTLS.dwg




- NOTES:**
- A GROOVE JOINT 1" DEEP WITH 1/8" RADI SHALL BE REQUIRED IN THE CONCRETE SIDEWALK AT 5' INTERVALS. ONE 1/2" EXPANSION JOINT WILL BE REQUIRED AT 45' INTERVALS NOT TO EXCEED 50' AND MATCHING EXPANSION/CONSTRUCTION JOINT IN ADJACENT CURB. A SEALED 1/2" EXPANSION JOINT WILL BE REQUIRED WHERE THE SIDEWALK JOINS ANY RIGID STRUCTURE.
 - SIDEWALK AT DRIVEWAY ENTRANCES TO BE 6" THICK.
 - WIDTH OF SIDEWALK ON THOROUGHFARE STREETS SHALL BE A MINIMUM OF 6'. WIDTH OF SIDEWALKS IN THE CENTRAL BUSINESS DISTRICT WILL BE DETERMINED BY THE CDOT.
 - WIDTH OF SIDEWALKS ON NON-THOROUGHFARE STREETS SHALL BE BASED ON TYPICAL STREET SECTION, A MINIMUM OF 5'. SIDEWALK TO BE POURED TO END OF RADIUS AT INTERSECTING STREETS.
 - CONCRETE COMPRESSIVE STRENGTH SHALL BE 3600 PSI. IN 28 DAYS.
 - ZONING CONDITIONS MAY REQUIRE ADDITIONAL WIDTH SIDEWALKS WHICH SHALL SUPERSEDE THESE STANDARD DIMENSIONS SHOWN.
 - LIDS FOR JUNCTION BOXES AND UTILITY VAULTS SHALL BE NON-SKID AS SPECIFIED BY ENGINEER.
 - JOINT MATERIALS SHALL LIMIT SHRINK/SWELL SO POST CONSTRUCTION INSTALLATION RESULTS IN A MAXIMUM OF 1/4" FROM FLUSH.

CONCRETE SIDEWALKS
Not to Scale




- NOTES:**
- CONCRETE FOR CURBING SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4,000 P.S.I. @ 28 DAYS.
 - CONSTRUCTION STAKING FOR CURB INSTALLATION SHALL BE REFERENCED (CUT OR FILL) TO THE TOP OF CURB.
 - AT CONTRACTOR'S OPTION, THE GUTTER THICKNESS MAY BE INCREASED AT THE EDGE OF PAVEMENT TO MAKE BOTTOM OF GUTTER CONTIGUOUS WITH BOTTOM OF ASPHALT PAVEMENT.
 - CONTRACTION JOINTS SHALL BE PLACED @ 10'-0" O.C. TOOLED 1/4" (±1/16") WIDE, 1" DEEP. EXPANSION JOINTS SHALL BE PLACED @ 40'-0" INTERVALS, MAXIMUM, AND ALL P.C.S.
 - GUTTER PAN SLOPE TO BE ADJUSTED WITHIN ACCESSIBLE PARKING SPACES TO MATCH SLOPE BETWEEN SPOT ELEVATIONS.


18" STANDARD CURB AND GUTTER
Not to Scale



SOLID PAVEMENT ARROWS
Not to Scale



CURB CUT (N.T.S.)



- NOTES:**
- ALL DETECTABLE WARNING DEVICES USED IN NEW CONSTRUCTION SHALL BE OF A RIGID PRECAST OR EMBEDDED PRODUCT APPROVED BY THE CITY ENGINEER. RETRO FIT MATS WILL ONLY BE ALLOWED ON EXISTING RAMPS WITH PRIOR APPROVAL OF THE CITY ENGINEER FOR MATERIAL, TYPE AND INSTALLATION (IE, RESURFACING).
 - RAMP AND DETECTABLE WARNING AREA SHALL BE A MINIMUM OF 4 FEET IN WIDTH, BUT NOT BE LESS THAN THE WIDTH OF SIDEWALK LEADING TO BACK OF RAMP.
 - DETECTABLE WARNING SURFACES SHALL EXTEND 2.0 FT MINIMUM IN THE DIRECTION OF PEDESTRIAN TRAVEL.
 - DETECTABLE WARNING AREA CAN BE SQUARE WHERE USED IN A CURB RADIUS.
 - THE ROWS OF TRUNCATED DOMES IN DETECTABLE WARNING SURFACES SHOULD BE ALIGNED PERPENDICULAR TO THE GRADE BREAK BETWEEN THE RAMP RUN AND THE STREET. WHERE DETECTABLE WARNING SURFACES ARE PROVIDED ON A SURFACE WITH A SLOPE THAT IS LESS THAN 5 PERCENT, DOME ORIENTATION IS LESS CRITICAL.
 - DETECTABLE WARNING AREA SHALL CONTRAST VISUALLY WITH ADJACENT WALKING SURFACES EITHER LIGHT-ON-DARK OR DARK-ON-LIGHT.
 - IF PAVERS ARE TO BE USED, PAVERS SHALL BE 6" THICK AND CAST FROM 5000 psi CONCRETE.
 - MATS ARE TO BE RIGID WITH TURN DOWN EDGES EMBEDDED IN CONCRETE TO ELIMINATE TRIP HAZARD.
 - LOCATE ENTIRE WARNING BEHIND CURB LINE TO MINIMIZE VEHICLES RIDING OVER THIS FEATURE.

DETECTABLE DOMES
Not to Scale



NO.	REVISIONS	DATE	BY

Kimley-Horn
© 2024 KIMLEY-HORN AND ASSOCIATES, INC.
200 SOUTH TRYON ST. SUITE 200, CHARLOTTE, NC 28202
WWW.KIMLEY-HORN.COM
FIRM COA NO. 51

STATE OF ARKANSAS
LICENSED PROFESSIONAL ENGINEER
No. 21699
BRYANT
NOT FOR CONSTRUCTION

KH PROJECT	014677008
DATE	05/28/2024
SCALE	AS SHOWN
DESIGNED BY	TTP
DRAWN BY	TTP
CHECKED BY	BMC

SITE DETAILS

WALGREENS #10240 - BRYANT, ARKANSAS
PREPARED FOR
WALGREENS COMPANY
BRYANT

SHEET NUMBER
C901

May 29, 2024

**Walgreens Store #10240 - Bryant
Modification Narrative**

This letter is to outline the modifications being proposed at the Walgreens site located at 5500 Highway 5 N, Bryant, AR 72022.

Due to the construction of the ARDOT roadway project no. 061335, the Walgreens' parking spaces located along Highway 5 frontage were taken out of compliance from the City's ordinance due to the loss in parking space depth. Therefore, we are proposing the removal of 10 of the existing 16 parking spaces. A landscaped island will replace the 10 parking spaces and contain a new sidewalk that connects the site's accessible route to the public sidewalk. This project will also require further coordination with ARDOT as we are working within their existing right-of-way.

If you have any further questions, please do not hesitate to contact me by phone at 479-388-1015 or by email at matt.cox@kimley-horn.com should you have any questions or need any addition information.

Thank you,

KIMLEY-HORN AND ASSOCIATES, INC.

Matt Cox, PE

SUBJECT PROPERTY

start Fence Installation



201 S. Elm St.
Big Dog Gym
Tonya Nichols
501-258-5462



City of Bryant Community Development
210 SW 3rd Street
Bryant, AR 72022
PHONE: 501-943-0857
FAX: 501-943-0992
EMAIL: tsmith@cityofbryant.com

Temporary Business Application and Information

- Applications are due by 5:00 Pm Wednesday the week prior to the scheduled Development Review Committee meeting.
- Application deadlines and meeting dates can be found on the City of Bryant's website under the Planning and Community Development page or by clicking [HERE](#).

Requirements for Submission

- Letter stating your request
- Complete and submit a Temporary Business Application
- Submit \$25.00 application fee
- Submit 8 copies of **site plan** showing:
 - Exact location of proposed temporary business including setbacks from streets or highway right-of-way.
 - Clearly identifying any open display areas.
 - The parking spaces to be dedicated by the owner of the property for use by this temporary business.
- Submit a letter from the property owner stating that they are in agreement with the site plan.
- If food establishment – show approval from **Arkansas Department of Health**.
- Provide \$1,000 surety bond made payable to City of Bryant conditioned for faithful performance of the payment of all applicable fees and penalties.

Temporary Business Application

City of Bryant

Date: 5/20/24

Name of Business: FIVE STAR FIREWORKS

Federal Tax Employer Identification Number: 453216207

Arkansas State Sales Tax Number: 55025123-~~668~~

Type of Business: RETAIL SALES

Location of proposed Temporary Business: 23395 I-30 BRYANT, ARK

Parcel Number of Location of proposed Temporary Business: 23395 I-30

Owner Mailing Address: P.O. BOX 6 BRYANT, ARK 72089

Contact Person: JEFF HOLDER

Daytime Phone Number: 501-350-6684 Evening Phone Number: 501-350-6684



Please check the category you are applying for. Permits cannot exceed the following time limits:

- | | | |
|-------------------------------------|--|----------|
| <input checked="" type="checkbox"/> | Carnivals | 30 Days |
| <input type="checkbox"/> | Fireworks stands or tents | 30 Days |
| <input type="checkbox"/> | Christmas tree stands, tents or lots | 60 Days |
| <input type="checkbox"/> | General commercial sales stands, tents or lots | 90 Days |
| <input type="checkbox"/> | Concession/Refreshment stands/Food Service | 180 Days |

Beginning Date Requested JUNE 20TH Ending Date Requested JULY 7TH

I hereby certify the above to be true and correct, and state that I am operating a business in accordance with the city's zoning regulations and/or any other city, state, or federal laws which may be applicable. I understand violation of Temporary Business Ordinance 2007-43 is a misdemeanor punishable by a fine of up to \$500.00 per occurrence of violation. Each day's occurrence is a separate violation. No temporary business may operate for more than 180 days during any consecutive 12-month period.

Owners Signature Mark Bradford



5/20/24

To the City of Bryant.

Hello my name is Mark Bradford.
I am the owner of Five Star Fireworks.
I am requesting to have ^{privilege} ~~privilege~~ to
retail Fireworks inside the city limits
of Bryant, Ark. I have previously done
business the past two years at the proposed
locations for this selling season. I follow
all rules, regulations, and ordinances that
have been established by the City of Bryant.
Please consider my business for this
upcoming fireworks season. Thank You

Mark Bradford
903-826-4453



City of Bryant Community Development
210 SW 3rd Street
Bryant, AR 72022
PHONE: 501-943-0857
FAX: 501-943-0992
EMAIL: tsmith@cityofbryant.com

Temporary Business Application and Information

- Applications are due by 5:00 Pm Wednesday the week prior to the scheduled Development Review Committee meeting.
- Application deadlines and meeting dates can be found on the City of Bryant's website under the Planning and Community Development page or by clicking [HERE](#).

Requirements for Submission

- Letter stating your request
- Complete and submit a Temporary Business Application
- Submit \$25.00 application fee
- Submit 8 copies of **site plan** showing:
 - Exact location of proposed temporary business including setbacks from streets or highway right-of-way.
 - Clearly identifying any open display areas.
 - The parking spaces to be dedicated by the owner of the property for use by this temporary business.
- Submit a letter from the property owner stating that they are in agreement with the site plan.
- If food establishment – show approval from **Arkansas Department of Health**.
- Provide \$1,000 surety bond made payable to City of Bryant conditioned for faithful performance of the payment of all applicable fees and penalties.

Temporary Business Application

City of Bryant

Date: 5/20/24

Name of Business: Five Star Fireworks

Federal Tax Employer Identification Number: 453216207

Arkansas State Sales Tax Number: 55025123

Type of Business: Retail Sales

Location of proposed Temporary Business: 5407 Hwy 5, Bryant, Ark.

Parcel Number of Location of proposed Temporary Business: 5407 Hwy 5

Owner Mailing Address: 5407 Hwy 5 Bryant, AR. 72084

Contact Person: BJ Grant

Daytime Phone Number: 501-847-3054 Evening Phone Number: 501-847-3051

Please check the category you are applying for. Permits cannot exceed the following time limits:

<input checked="" type="checkbox"/>	Carnivals	30 Days
<input type="checkbox"/>	Fireworks stands or tents	30 Days
<input type="checkbox"/>	Christmas tree stands, tents or lots	60 Days
<input type="checkbox"/>	General commercial sales stands, tents or lots	90 Days
<input type="checkbox"/>	Concession/Refreshment stands/Food Service	180 Days

Beginning Date Requested June 20th, 24 Ending Date Requested July

I hereby certify the above to be true and correct, and state that I am operating a business in accordance with the city's zoning regulations and/or any other city, state, or federal laws which may be applicable. I understand violation of Temporary Business Ordinance 2007-43 is a misdemeanor punishable by a fine of up to \$500.00 per occurrence of violation. Each day's occurrence is a separate violation. No temporary business may operate for more than 180 days during any consecutive 12-month period.

Owners Signature Mark Bradford

5/20/24


To the City of Bryant.

Hello my name is Mark Bradford.
I am the owner of Fire Star Fireworks.
I am requesting to have ~~privilege~~^{privilege} to
retail Fireworks inside the city limits
of Bryant, Ark. I have previously done
business the past two years at the proposed
locations for this selling season. I follow
all rules, regulations, and ordinances that
have been established by the City of Bryant.
Please consider my business for this
upcoming fireworks season. Thank You

Mark Bradford
903-826-4453




BUILDINGS



BANK

PARKING

PARKING



DRIVEWAY

5407 Hwy 5
Bryant, Ark

Hwy 5

2516 Springhill Rd

Location

Flood

Fire

Heat

> id

Hurricane Lake
Baptist Church

*New
Building*

*Fellowship
Hall*

*Proposed
Awning
8' X 84'*

2516





City of Bryant, Arkansas
 Community Development
 210 SW 3rd Street Bryant, AR 72022
 501-943-0943



Temporary Business Application For the Sale of Fireworks

- Applications are due by 5:00PM Wednesday the week prior to the Scheduled Development and Review Committee Meeting.
- Application Deadlines and dates can be found at www.cityofbryant.com under the Community Development tab.

Date: 6/6/24

Business Information:

Name Arnold's Fireworks

Federal Tax Employer ID Number 710311720

Arkansas State Sales Tax Number 034327-60-001

Location of Proposed Temporary Business Peter Cunningham First Southern Baptist Church
 (SAME LOCATION AS LAST YEAR) 604 South Reynolds Rd.
501-909-9779

Business Owner:

Contact Person:

Name Tom Daniel

Name TERRY HARPER

Address 4802 Lexington Park Cir.
BRYANT, AR

Address 3208 S. Shust Rd
BRYANT, AR

Phone 501-758-2624

Phone 501-590-8007

Email ARKANSAS TENT@YAHOO.COM

Email THARPER1777@GMAIL.COM

Checklist for Submission

- Completed Application and Checklist
- Twenty-Five Dollar (\$25.00) Application fee
- Provide proof of 1,000,000 Liability Insurance or Surety Bond worth the same amount.
 (Further information on the details of liability insurance can be found in Section 2-4 of the Temporary Business Section of the Bryant Business Ordinance.)

- Eight (8) copies of a **Site Plan**:
 - Site Plan shall be to scale, all structures shall be identified. Clear identification of any open display areas
 - Fireworks tent / canopy shall have a minimum 50ft. setback from all other structures
 - Show parking spaces dedicated by the owner of the property for use by the temporary business.
- Exits shall be provided every 100 ft. with a minimum of 2 remotely located exits
Minimum exit width shall be 72 in. All exits shall be identified with proper signage
- No smoking permitted within 50 ft. of firework tent / canopy. "NO SMOKING" signs shall be posted at all entrance / exits
- 2 ABC fire extinguishers, with a 2A rating or greater, shall be provided. The maximum travel distance to an extinguisher shall not exceed 75 ft. Additional extinguishers may be required. Extinguishers shall be clearly visible, marked with appropriate signage, and mounted height of not less than 36 in. from the ground
- Generators or other combustion power sources, including fuel, shall be separated from tents / canopies by a minimum of 25 ft.
- Applicant shall contact the Bryant Fire Dept. Fire Marshal's office and schedule an inspection once the business is ready for operation. The inspection shall be conducted prior to any sales to the public are allowed. Contact: 501-943-0964

READ CAREFULLY BEFORE SIGNING

I Tom Daniel, do hereby certify that all information contained within this application is true and correct. I further certify that I agree too and will abide by all Temporary Business rules and regulations as outlined in the Bryant Business Ordinance. I also understand that I shall comply with all additional applicable ordinances of the City as well as the requirements of all state and federal laws. Furthermore, I understand violation of Temporary Business Ordinance 2007-43 is a misdemeanor punishable by a fine of up to \$500.00 per occurrence of violation. Each day's occurrence is a separate violation.

Owners Signature Tom Daniel



30' x 40' Tent



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)
05/31/2024

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER PROFESSIONAL PROGRAM INSURANCE BROKERAGE DIVISION OF SPG INSURANCE SOLUTIONS, LLC 1304 SOUTHPPOINT BLVD., #101 PETALUMA CA 94954	CONTACT NAME: PHONE (A/C, No, Ext): 415-475-4300 FAX (A/C, No): 415-475-4303 E-MAIL ADDRESS:	
	INSURER(S) AFFORDING COVERAGE NAIC # INSURER A : Certain Underwriters at Lloyd's, London AA-1128623 INSURER B : INSURER C : INSURER D : INSURER E : INSURER F :	
INSURED Arnold Fireworks, Inc.; Spa Fireworks, Co. PO Box 873 N. Little Rock AR 72115		


COVERAGES **CERTIFICATE NUMBER:** BL-000911 **REVISION NUMBER:**

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS	
A	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input checked="" type="checkbox"/> CLAIMS-MADE <input type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input checked="" type="checkbox"/> POLICY <input type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC OTHER:	X		PY/24-0050	04/30/2024	04/30/2025	EACH OCCURRENCE	\$ \$1,000,000
	DAMAGE TO RENTED PREMISES (Ea occurrence)						\$ \$50,000	
	AUTOMOBILE LIABILITY <input type="checkbox"/> ANY AUTO <input type="checkbox"/> OWNED AUTOS ONLY <input type="checkbox"/> SCHEDULED AUTOS <input type="checkbox"/> HIRED AUTOS ONLY <input type="checkbox"/> NON-OWNED AUTOS ONLY						COMBINED SINGLE LIMIT (Ea accident)	\$
	UMBRELLA LIAB <input type="checkbox"/> OCCUR EXCESS LIAB <input type="checkbox"/> CLAIMS-MADE DED RETENTION \$						EACH OCCURRENCE	\$
	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below						PER STATUTE OTH-ER	
							E.L. EACH ACCIDENT	\$
							E.L. DISEASE - EA EMPLOYEE	\$
							E.L. DISEASE - POLICY LIMIT	\$

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

Albert Arey are Additional Insured as respects the retail fireworks stand, located at 2625 Springhill Rd, Bryant, AR 72019 operating from 06/24/2024 through 07/07/2024.

CERTIFICATE HOLDER Albert Arey 2625 Springhill Rd Bryant AR 72019	CANCELLATION SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS. AUTHORIZED REPRESENTATIVE 
---	--



Permit Number
FWL.0001220

THIS LICENSE MUST BE CONSPICUOUSLY DISPLAY IN PLACE OF BUSINESS

Office of Fire Services

State Fire Marshal



Date of Issue
05/01/2023

FIREWORKS LICENSE


This is to certify that
Arnold Fireworks, Inc.
is duly license to transact business in the State of Arkansas as a Fireworks:
IMPORTER LICENSE

LICENSE EXPIRES

04/30/2025

AJ GARY

DIRECTOR and STATE
HOMELAND SECURITY ADVISOR



NON TRANSFERABLE

Jake Dennis Free

Jake Dennis Free
STATE FIRE MARSHAL

State of Arkansas
ARKANSAS SALES AND USE TAX PERMIT

ARNOLD FIREWORKS INC

DATE ISSUED:

P O BOX 873

PERMIT NUMBER: 034327-60-001

N LITTLE ROCK AR 72115

DLN:

DATE OPENED: 05/01/1971

SIC: 5042

TOYS AND HOBBY GOODS AND SUPPLIES

EXEMPTION: 81 THIS BUSINESS IS EXEMPT FROM SALES TAX, ONLY FOR THE PURCHASES OF GOODS TO BE RESOLD IN THE NORMAL COURSE OF BUSINESS.



THIS PERMIT IS VALID UNTIL IT IS CANCELED AND SURRENDERED BY THE PERMIT HOLDER OR REVOKED BY THE COMMISSIONER OF REVENUE.

THIS PERMIT MUST BE SURRENDERED IF BUSINESS IS SOLD, DISCONTINUED OR LOCATION CHANGED.

WHEN THIS PERMIT IS SURRENDERED FOR ANY OF THE ABOVE REASONS, YOU MUST REPORT AND PAY ANY SALES OR USE TAX PLUS ANY PENALTIES OR INTEREST THAT IS OWED BY THIS BUSINESS. FAILURE TO PAY THESE TAXES WILL RESULT IN A LIEN BEING PLAID AGAINST THE STOCK AND FIXTURES OF THIS BUSINESS AND THE SAME IS ENFORCEABLE AGAINST PURCHASERS AND THIRD PARTIES.

THIS PERMIT MUST BE DISPLAYED IN A PROMINENT PLACE IN YOUR BUSINESS IN



City of Bryant, Arkansas
 Community Development
 210 SW 3rd Street Bryant, AR 72022
 501-943-0943



Temporary Business Application For the Sale of Fireworks

- Applications are due by 5:00PM Wednesday the week prior to the Scheduled Development and Review Committee Meeting.
- Application Deadlines and dates can be found at www.cityofbryant.com under the Community Development tab.

Date: 6/6/24

Business Information:

Name Arnold's Fireworks
 Federal Tax Employer ID Number 710311720
 Arkansas State Sales Tax Number 034327-60-001
 Location of Proposed Temporary Business ALBERT ARCY 2625 SPRINGLICK Rd, BRYANT
(Same Location as last year) 501-454-1252

Business Owner:

Name Tom Daniel
 Address 4802 LEXINGTON PARK CR.
BRYANT, AR
 Phone 501-758-2624
 Email ARKANSAS TENT@YAHOO.COM

Contact Person:

Name TERRY HARPER
 Address 3208 S. SHORE Rd
BRYANT, AR
 Phone 501-590-8007
 Email THARPER1777@GMAIL.COM

Checklist for Submission

- Completed Application and Checklist
- Twenty-Five Dollar (\$25.00) Application fee
- Provide proof of 1,000,000 Liability Insurance or Surety Bond worth the same amount.
 (Further information on the details of liability insurance can be found in Section 2-4 of the Temporary Business Section of the Bryant Business Ordinance.)

(Continued on Page 2)

- Eight (8) copies of a **Site Plan**:
 - Site Plan shall be to scale, all structures shall be identified. Clear identification of any open display areas
 - Fireworks tent / canopy shall have a minimum 50ft. setback from all other structures
 - Show parking spaces dedicated by the owner of the property for use by the temporary business.
- Exits shall be provided every 100 ft. with a minimum of 2 remotely located exits
Minimum exit width shall be 72 in. All exits shall be identified with proper signage
- No smoking permitted within 50 ft. of firework tent / canopy. "NO SMOKING" signs shall be posted at all entrance / exits
- 2 ABC fire extinguishers, with a 2A rating or greater, shall be provided. The maximum travel distance to an extinguisher shall not exceed 75 ft. Additional extinguishers may be required. Extinguishers shall be clearly visible, marked with appropriate signage, and mounted height of not less than 36 in. from the ground
- Generators or other combustion power sources, including fuel, shall be separated from tents / canopies by a minimum of 25 ft.
- Applicant shall contact the Bryant Fire Dept. Fire Marshal's office and schedule an inspection once the business is ready for operation. The inspection shall be conducted prior to any sales to the public are allowed. Contact: 501-943-0964

READ CAREFULLY BEFORE SIGNING

I, Tom Daniel, do hereby certify that all information contained within this application is true and correct. I further certify that I agree too and will abide by all Temporary Business rules and regulations as outlined in the Bryant Business Ordinance. I also understand that I shall comply with all additional applicable ordinances of the City as well as the requirements of all state and federal laws. Furthermore, I understand violation of Temporary Business Ordinance 2007-43 is a misdemeanor punishable by a fine of up to \$500.00 per occurrence of violation. Each day's occurrence is a separate violation.

Owners Signature Tom Daniel



30' x 40' TENT



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)
05/31/2024

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an **ADDITIONAL INSURED**, the policy(ies) must have **ADDITIONAL INSURED** provisions or be endorsed. If **SUBROGATION IS WAIVED**, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER		CONTACT NAME:	
PROFESSIONAL PROGRAM INSURANCE BROKERAGE		PHONE (A/C, No, Ext): 415-475-4300	FAX (A/C, No): 415-475-4303
DIVISION OF SPG INSURANCE SOLUTIONS, LLC		E-MAIL ADDRESS:	
1304 SOUTHPOINT BLVD., #101		INSURER(S) AFFORDING COVERAGE	
PETALUMA CA 94954		INSURER A: Certain Underwriters at Lloyd's, London	NAIC # AA-1128623
INSURED		INSURER B:	
Arnold Fireworks, Inc.; Spa Fireworks, Co.		INSURER C:	
PO Box 873		INSURER D:	
N. Little Rock AR 72115		INSURER E:	
		INSURER F:	

COVERAGES**CERTIFICATE NUMBER:** BL-000909**REVISION NUMBER:**

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
A	<input checked="" type="checkbox"/> COMMERCIAL GENERAL LIABILITY <input checked="" type="checkbox"/> CLAIMS-MADE <input type="checkbox"/> OCCUR GEN'L AGGREGATE LIMIT APPLIES PER: <input checked="" type="checkbox"/> POLICY <input type="checkbox"/> PRO-JECT <input type="checkbox"/> LOC OTHER:			PY/24-0050	04/30/2024	04/30/2025	EACH OCCURRENCE \$ \$1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$ \$50,000 MED EXP (Any one person) \$ PERSONAL & ADV INJURY \$ GENERAL AGGREGATE \$ \$1,000,000 PRODUCTS - COMP/OP AGG \$ INCLUDED \$
	AUTOMOBILE LIABILITY <input type="checkbox"/> ANY AUTO <input type="checkbox"/> OWNED AUTOS ONLY <input type="checkbox"/> SCHEDULED AUTOS NON-OWNED AUTOS ONLY <input type="checkbox"/> HIRED AUTOS ONLY						COMBINED SINGLE LIMIT (Ea accident) \$ BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$
	<input type="checkbox"/> UMBRELLA LIAB <input type="checkbox"/> EXCESS LIAB <input type="checkbox"/> OCCUR <input type="checkbox"/> CLAIMS-MADE <input type="checkbox"/> DED <input type="checkbox"/> RETENTION \$						EACH OCCURRENCE \$ AGGREGATE \$ \$
	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below						<input type="checkbox"/> PER STATUTE <input type="checkbox"/> OTH-ER E.L. EACH ACCIDENT \$ E.L. DISEASE - EA EMPLOYEE \$ E.L. DISEASE - POLICY LIMIT \$

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)

Peter Cunningham are Additional Insured as respects the retail fireworks stand, located at 604 S Reynolds Rd, Bryant, AR 72022 operating from 06/24/2024 through 07/07/2024.

CERTIFICATE HOLDER**CANCELLATION**1st Southern Baptist Church

604 S Reynolds Rd

Bryant AR 72022

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

© 1988-2015 ACORD CORPORATION. All rights reserved.



Permit Number
FW1.0001220

THIS LICENSE MUST BE CONSPICUOUSLY DISPLAY IN PLACE OF BUSINESS

Office of Fire Services

State Fire Marshal



Date of Issue
05/01/2023

FIREWORKS LICENSE

This is to certify that

Arnold Fireworks, Inc.

is duly license to transact business in the State of Arkansas as a Fireworks:

IMPORTER LICENSE

LICENSE EXPIRES

04/30/2025

AJ GARY

DIRECTOR and STATE
HOMELAND SECURITY ADVISOR



NON TRANSFERABLE

Jake Dennis Free

Jake Dennis Free
STATE FIRE MARSHAL

State of Arkansas
ARKANSAS SALES AND USE TAX PERMIT

ARNOLD FIREWORKS INC

DATE ISSUED:

P O BOX 873

PERMIT NUMBER: 034327-60-001

N LITTLE ROCK AR 72115


DLN:

DATE OPENED: 05/01/1971

SIC: 5042

TOYS AND HOBBY GOODS AND SUPPLIES

EXEMPTION: 81 THIS BUSINESS IS EXEMPT FROM SALES TAX ONLY FOR THE PURCHASES OF GOODS TO BE RESOLD IN THE NORMAL COURSE OF BUSINESS.





THIS PERMIT IS VALID UNTIL IT IS CANCELLED AND SURRENDERED BY THE PERMIT HOLDER OR REVOKED BY THE COMMISSIONER OF REVENUE.

THIS PERMIT MUST BE SURRENDERED IF BUSINESS IS SOLD, DISCONTINUED OR LOCATION CHANGED.

WHEN THIS PERMIT IS SURRENDERED FOR ANY OF THE ABOVE REASONS, YOU MUST REPORT AND PAY ANY SALES OR USE TAX PLUS ANY PENALTIES OR INTEREST THAT IS OWED BY THIS BUSINESS. FAILURE TO PAY THESE TAXES WILL RESULT IN A LIEN BEING PLACED AGAINST THE STOCK AND ASSETS OF THIS BUSINESS AND THE SAME IS ENFORCEABLE AGAINST PURCHASERS AND THIRD PARTIES.

THIS PERMIT MUST BE DISPLAYED IN A PROMINENT PLACE IN YOUR BUSINESS XX



CERTIFICATE OF OWNER:
 We, the undersigned, owners of the real estate shown and described herein do hereby certify that we have caused to be laid off, platted and subdivided, and to hereby lay off, plat and subdivide said real estate in accordance with the plat.

Date of Execution: _____ Name: _____
 Source of Title: WARRANTY DEED 2020-008135

CERTIFICATE OF FINAL SURVEYING ACCURACY:
 I, William Corbett R. Shoffner, hereby certify that this plat correctly represents a survey and a plan made by me or under my supervision; that all monuments shown hereon actually exist and their location, size, type and material are correctly shown; and that all interior lot lines have been adjusted to "as built conditions" and are accurately described on the plat and identified on the ground in terms of length and direction of the property sides.

Date of Execution _____ William Corbett R. Shoffner
 Registered Professional
 Land Surveyor No. 1664 Arkansas

CERTIFICATE OF AUTHORIZATION
 HOPE CONSULTING, INC.
 No. 1937
 ARKANSAS

REGISTERED PROFESSIONAL LAND SURVEYOR
 STATE OF ARKANSAS
 No. 1664
 SIGNATURE

CERTIFICATE OF FINAL PLAT APPROVAL:
 Pursuant to the City of Bryant Subdivision Rules and Regulations, this document was given approval by the Bryant Planning Commission at a meeting held _____, 20____.
 All Documents are hereby accepted, and this certificate is hereby executed under the authority of said rules and regulations.

Date of Execution _____ Name _____
 Bryant Planning Commission Chairman

PROPERTY DESCRIPTION FROM SURVEY
 TRACT 1
 A PART OF THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER (SW1/4, SE1/4) OF SECTION 9, TOWNSHIP 5 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS:
 BEGINNING AT A 2-1/2" ALUMINUM MONUMENT MARKING THE SOUTHWEST CORNER OF SAID SW1/4, SE1/4, OF SECTION 9;
 THENCE NORTH 07°49'05" EAST ALONG THE WEST LINE THEREOF A DISTANCE OF 821.57 FEET TO POINT;
 THENCE LEAVING SAID WEST LINE NORTH 89°44'37" EAST A DISTANCE OF 453.83 FEET TO A FND. 5/8" REBAR & CAP (PS 1506);
 THENCE SOUTH 02°02'23" WEST A DISTANCE OF 831.76 FEET TO A MAG NAIL (PS 1664) IN HILLTOP ROAD ON THE SOUTH LINE OF SAID SW1/4, SE1/4, OF SECTION 9;
 THENCE ALONG SAID SOUTH LINE NORTH 88°38'36" WEST A DISTANCE OF 450.35 FEET TO THE POINT OF BEGINNING, CONTAINING 373,505.14 SQUARE FEET, OR 8.58 ACRES, MORE OR LESS.

FLOOD ZONE INFORMATION
 NO PORTION OF THE PROPERTY DESCRIBED HEREON LIES WITHIN A SPECIAL FLOOD HAZARD AREA, ACCORDING TO THE FEMA FLOOD INSURANCE RATE MAP LISTED BELOW:
 PANEL # 05125C0325E, DATED: 06/05/2020

PROPERTY DESCRIPTION FROM SURVEY
 TRACT 2
 A PART OF THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER (SW1/4, SE1/4) AND THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER (SE1/4, SE1/4) OF SECTION 9, TOWNSHIP 5 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS:
 COMMENCING AT A 2-1/2" ALUMINUM MONUMENT MARKING THE SOUTHWEST CORNER OF SAID SW1/4, SE1/4, OF SECTION 9;
 THENCE NORTH 07°49'05" EAST ALONG THE WEST LINE THEREOF A DISTANCE OF 821.57 FEET TO POINT;
 THENCE LEAVING SAID WEST LINE NORTH 89°44'37" EAST A DISTANCE OF 453.83 FEET TO A FND. 5/8" REBAR & CAP (PS 1506) AND THE POINT OF BEGINNING;
 THENCE SOUTH 02°02'23" WEST A DISTANCE OF 831.76 FEET TO A MAG NAIL (PS 1664) IN HILLTOP ROAD ON THE SOUTH LINE OF SAID SW1/4, SE1/4, OF SECTION 9;
 THENCE NORTH 88°37'35" WEST A DISTANCE OF 465.97 FEET TO A FND. 1/2" REBAR;
 THENCE SOUTH 07°17'14" EAST A DISTANCE OF 1000.11 FEET TO A FND. 1/2" REBAR;
 THENCE SOUTH 89°42'44" EAST A DISTANCE OF 1000.02 FEET TO A FND. 1/2" REBAR;
 THENCE NORTH 07°08'50" WEST A DISTANCE OF 1000.03 FEET TO A FND. 1/2" REBAR;
 THENCE NORTH 88°39'55" EAST A DISTANCE OF 635.46 FEET TO A FND. 1/2" PIPE AND THE NORTHWEST CORNER OF SAID, SE1/4, SE1/4, OF SECTION 9 ON THE WEST LINE OF LOMBARD HEIGHTS SUBDIVISION, PHASE 2, AS FILED FOR RECORD AS INSTRUMENT 2023-002306;
 THENCE ALONG SAID WEST LINE SOUTH 07°35'03" WEST A DISTANCE OF 63.20 FEET

TO A FND. 5/8" REBAR AND THE SOUTHWESTERN-MOST CORNER OF LOT 40 OF SAID LOMBARD HEIGHTS, PHASE 2;
 THENCE ALONG THE SOUTH LINE OF SAID LOMBARD HEIGHTS, PHASE 2, SOUTH 88°39'36" EAST A DISTANCE OF 869.49 FEET TO A SET 1/2" REBAR & CAP (PS 1664) ON THE SOUTH LINE OF LOT 30 OF SAID LOMBARD HEIGHTS, PHASE 2;
 THENCE SOUTH 70°39'54" EAST A DISTANCE OF 55.24 FEET TO A SET 1/2" REBAR & CAP (PS 1664) AT THE SOUTHWEST CORNER OF LOT 30 OF SAID LOMBARD HEIGHTS, PHASE 2;
 THENCE ALONG THE SOUTH LINE OF SAID LOT 30 SOUTH 89°33'49" EAST A DISTANCE OF 120.02 FEET TO THE SOUTHEAST CORNER THEREOF;
 THENCE LEAVING SAID SOUTH LINE SOUTH 07°42'20" WEST A DISTANCE OF 568.8 FEET TO A 5/8" REBAR & CAP (PS 568);
 THENCE NORTH 88°37'35" WEST A DISTANCE OF 467.02 FEET TO A FND. 5/8" REBAR & CAP (PS 568);
 THENCE NORTH 88°52'07" WEST A DISTANCE OF 467.72 FEET TO A FND. 5/8" REBAR & CAP (PS 568);
 THENCE NORTH 88°59'03" WEST A DISTANCE OF 339.43 FEET TO A FND. 5/8" REBAR;
 THENCE SOUTH 02°17'06" WEST A DISTANCE OF 660.32 FEET TO A SET 1/2" REBAR & CAP (PS 1664) ON THE SOUTH LINE OF SAID SE1/4, SE1/4, OF SECTION 9;
 THENCE ALONG SAID SOUTH LINE NORTH 88°38'36" WEST A DISTANCE OF 1,236.57 FEET TO A MAG NAIL (PS 1664) IN HILLTOP ROAD;
 THENCE LEAVING SAID SOUTH LINE NORTH 88°38'36" WEST A DISTANCE OF 831.76 FEET TO THE POINT OF BEGINNING, CONTAINING 1,973,470.21 SQUARE FEET, OR 45.39 ACRES, MORE OR LESS.

RECORD PROPERTY DESCRIPTION
 A PORTION OF SALINE COUNTY INSTRUMENT DEED 2020-008135

REFERENCE DOCUMENTS CITED
 RECORDED SURVEY PLATS BY:
 RASBERRY (PS 1506), DATED 8-14-200, FOR THOMPSON SHAMBERGER (PS 1588), DATED 6-2-2007, FOR JONES

SURVEY DETAILS AND NOTES
 OWNER OF RECORD: NXT GEN HOMES, LLC
 PHYSICAL ADDRESS: HILLTOP RD AND MILLER RD
 COUNTY PARCEL TAX ID: PART OF 840-1625-025
 CURRENT ZONING: R-2 RESIDENTIAL DISTRICT

ALL DIMENSIONS LISTED ARE AS MEASURED BY THIS SURVEYOR UNLESS OTHERWISE NOTED. FOR RECORD DIMENSIONS SEE DOCUMENTS OF RECORD.

OWNERSHIP INFORMATION, IF SHOWN, IS LISTED AS PUBLISHED BY THE LOCAL COUNTY TAX ASSESSOR AND IS LISTED FOR REFERENCE ONLY. NO STATEMENTS OF OWNERSHIP, RIGHTS, OR INTERESTS ARE MADE.

THIS SURVEY IS BASED ON PUBLIC RECORDS AND/OR TITLE INVESTIGATIONS FURNISHED BY THIRD PARTIES. NO INDEPENDENT SEARCH OR INVESTIGATION HAS BEEN MADE BY THIS FIRM FOR ANY RECORDS, PUBLIC OR PRIVATE, LISTED REFERENCE DOCUMENTS HEREON WERE USED AND CONSIDERED AS A PART OF THIS SURVEY; HOWEVER OTHER RECORDS, IF ANY, COULD FURTHER AFFECT THIS SURVEY. NO STATEMENT OR GUARANTEES OF OWNERSHIP, RIGHTS, OR OTHER INTERESTS ARE MADE BY THIS SURVEY PLAT.

TYPICAL LOT SETBACKS:
 FRONT: 25 FEET
 SIDE (EXTERIOR): 15 FEET
 SIDE: 8 FEET
 REAR: 25 FEET

TYPICAL UTILITY & DRAINAGE EASEMENTS:
 FRONT: 5 FEET
 SIDE: 5 FEET
 REAR: 5 FEET

LEGEND

- - PLSS Aliquot Corner
- - Fnd. Corner Monument
- △ - Computed Point
- (M) - As Measured
- (P) - Per Deed or Plat Records
- ESMT - Easement
- B.S.L. - Building Setback Lines
- Clean Out
- Water Meter
- Power Pole
- Sewer Manhole
- Light Pole
- Telephone Pedestal
- Drainage Manhole
- Gas Meter
- Fence
- Overhead Power
- Sewer Line
- Water Line
- Telephone Line
- Electric Line
- Gas Line

HOPE CONSULTING ENGINEERS - SURVEYORS
 129 North Main Street
 Benton, Arkansas 72015
 Office: (501) 315-2626 | Fax: (501) 315-0024
 www.HopeConsulting.com

TRACT SPLIT
 PART OF THE SE 1/4, SE1/4 & PART OF THE SW1/4, SE 1/4, SECTION 9, TOWNSHIP 5, RANGE 14 W, SALINE COUNTY, ARKANSAS

FOR USE AND BENEFIT OF:
 NXT GEN HOMES, LLC

CORNER OF HILLTOP RD & MILLER RD
 ALEXANDER, ARKANSAS, 72002

DATE: 06/20/2024
 REVISION: _____
 SHEET: 1 OF 1

CAD BY: CV
 CHECKED BY: _____
 SCALE: 1" = 100'

PROJECT NUMBER:
24-0752

AR STATE LAND SURVEY FILING CODE: 500 - 01S - 14W - 0 - 09 - 200 - 62 - 1664



THOMAS ENGINEERING COMPANY

civil engineers

land surveyors

3810 LOOKOUT RD

NORTH LITTLE ROCK, AR 72116

(501)753-4463

NATIONAL SOCIETY OF PROFESSIONAL ENGINEERS

June 19, 2024

Mr. Colton Leonard
City of Community Development
210 SW 3rd Street
Bryant, AR 72022

RE: Civil Site Plans and Preliminary Plat
Little Caesars

Dear Mr. Leonard:

Please accept this letter as our application for the above referenced submittal.

The owner is requesting a site plan review and preliminary final plat of Lot 1, Little Caesars Addition to the City of Bryant to allow the construction of a Little Caesars Restaurant and associated parking.


If you have any questions, please give me a call.

Sincerely,

John R. Pownall, P.E.
President

JRP/ab

cc: Mike Fritz
Chris Smith



VICINITY MAP

THIS SITE




SURVEY LEGAL DESCRIPTION:

PART OF THE SE1/4 NW1/4 OF SECTION 27, TOWNSHIP 1 SOUTH, RANGE 14 WEST, IN THE CITY OF BRYANT, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF SAID SE1/4 NW1/4;
 THENCE ALONG THE WEST LINE OF THE SAID SE1/4 NW1/4 S 00° 00' 00" E FOR 1143.40 FEET;
 THENCE N 87° 59' 54" E FOR 530.36 FEET LEAVING THE WEST LINE OF SAID SE1/4 NW1/4 TO A TO 5/8" REBAR AND THE POINT OF BEGINNING;
 THENCE N 13° 04' 16" W FOR 193.28 FEET TO A 5/8" REBAR AND THE SOUTHERLY RIGHT OF WAY LINE OF BROWN LANE;
 THENCE ALONG SAID RIGHT OF WAY LINE S 89° 20' 38" E FOR 195.38 FEET TO A 1/2" REBAR AND THE WESTERLY RIGHT OF WAY LINE OF NORTH REYNOLDS ROAD;
 THENCE ALONG SAID RIGHT OF WAY LINE S 14° 49' 14" E FOR 194.54 FEET TO A 1/2" REBAR;
 THENCE N 89° 25' 16" W FOR 201.43 FEET TO THE POINT OF BEGINNING.

LEGEND

- SHOWS EXISTING STREETS.
- SHOWS SEWER, UTILITY AND DRAINAGE EASEMENT.
- SHOWS BUILDING SETBACK LINE
- SHOWS SURVEY MONUMENT AS DESCRIBED



CERTIFICATE OF SURVEYING ACCURACY

I, JOHN R. POWNALL, HEREBY CERTIFY THAT THIS PLAT REPRESENTS A BOUNDARY SURVEY MADE BY ME AND THAT BOUNDARY MARKERS SHOWN HEREON ACTUALLY EXIST AND THEIR LOCATION, TYPE AND MATERIAL ARE CORRECTLY SHOWN.

DATE _____ JOHN R. POWNALL RLS 1215

CERTIFICATE OF ENGINEERING ACCURACY

I, JOHN R. POWNALL, HEREBY CERTIFY THAT THIS PLAT REPRESENTS A PLAN MADE BY ME, AND THAT IT MEETS ALL THE ENGINEERING REQUIREMENTS OF THE BRYANT SUBDIVISION RULES AND REGULATIONS.

DATE _____ JOHN R. POWNALL PE 4685

CERTIFICATE OF OWNER

WE, THE UNDERSIGNED, OWNERS OF THE REAL ESTATE SHOWN AND DESCRIBED HEREON, HEREBY CERTIFY THAT WE HEREBY LAY OFF, PLAT, AND SUBDIVIDE SAID REAL ESTATE IN ACCORDANCE WITH THIS PLAT.

DATE _____ NAME _____

CERTIFICATE OF FINAL APPROVAL

PURSUANT TO THE BRYANT SUBDIVISION RULES AND REGULATIONS, AND ALL OF THE CONDITIONS OF APPROVAL HAVING BEEN COMPLETED, THIS DOCUMENT IS HEREBY ACCEPTED. THIS CERTIFICATE IS HEREBY EXECUTED UNDER THE AUTHORITY OF SAID RULES AND REGULATIONS.




DATE _____ BRYANT PLANNING COMMISSION CHAIRMAN

OWNER & DEVELOPER:
 OBWAT HOLDINGS, LLC
 7500 LANDERS ROAD
 SHERWOOD, AR. 72117

PLAT OF
 LOT 1 LITTLE CAESARS ADDITION
 IN
 THE CITY OF BRYANT
 AND IN
 SE1/4 & NW1/4 SECTION 27
 TOWNSHIP 1 SOUTH, RANGE 14 WEST
 SALINE COUNTY, ARKANSAS

GENERAL NOTES

- THIS PROPERTY IS ZONED C2.
- THIS PROPERTY IS NOT SHOWN IN THE 100 YEAR FLOOD PLAIN ON THE FLOOD INSURANCE RATE MAP COMMUNITY PANEL NUMBER 050308 0380 E DATED JUNE 5, 2020.
- BASIS OF BEARINGS: ARKANSAS STATE PLAIN, NAD 1983, SOUTH ZONE.



TE THOMAS ENGINEERING COMPANY
 3810 LOOKOUT ROAD, N. LITTLE ROCK, AR. 72116
 TEL: 501-753-4463 FAX: 501-753-6814

PLAT LOT 1 LITTLE CAESARS ADDITION BRYANT, ARK.			
APPROVED	DRAWN BY	DATE	SHEET NO.
	MJC	6/20/24	1
SCALE 1" = 20'			

LITTLE CAESARS-BRYANT-23-0165.dwg

PLOTTED: 6/20/2024



