

CERTIFICATE OF OWNER:
 We, the undersigned, owners of the real estate shown and described herein do hereby certify that we have caused to be laid off, platted and subdivided, and to hereby lay off, plat and subdivide said real estate in accordance with the plat.

Date of Execution: _____ Name: _____
 Source of Title: WARRANTY DEED 2020-008135

CERTIFICATE OF FINAL SURVEYING ACCURACY:
 I, William Corbett R. Shoffner, hereby certify that this plat correctly represents a survey and a plan made by me or under my supervision; that all monuments shown hereon actually exist and their location, size, type and material are correctly shown; and that all interior lot lines have been adjusted to "as built conditions" and are accurately described on the plat and identified on the ground in terms of length and direction of the property sides.


Date of Execution _____ William Corbett R. Shoffner
 Registered Professional
 Land Surveyor No. 1664 Arkansas

CERTIFICATE OF AUTHORIZATION
 HOPE CONSULTING, INC.
 No. 1937
 ARKANSAS

REGISTERED PROFESSIONAL LAND SURVEYOR
 WILLIAM CORBETT R. SHOFFNER
 No. 1664
 ARKANSAS

CERTIFICATE OF FINAL PLAT APPROVAL:
 Pursuant to the City of Bryant Subdivision Rules and Regulations, this document was given approval by the Bryant Planning Commission at a meeting held _____, 20____.
 All documents are hereby accepted, and this certificate is hereby executed under the authority of said rules and regulations.

Date of Execution _____ Name _____
 Bryant Planning Commission Chairman



PROPERTY DESCRIPTION FROM SURVEY
 TRACT 1
 A PART OF THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER (SW1/4, SE1/4) OF SECTION 9, TOWNSHIP 5 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS:
 BEGINNING AT A 2-1/2" ALUMINUM MONUMENT MARKING THE SOUTHWEST CORNER OF SAID SW1/4, SE1/4, OF SECTION 9;
 THENCE NORTH 07°49'03" EAST ALONG THE WEST LINE THEREOF A DISTANCE OF 821.57 FEET TO POINT;
 THENCE LEAVING SAID WEST LINE NORTH 89°44'37" EAST A DISTANCE OF 453.83 FEET TO A FND. 5/8" REBAR & CAP (PS 1506);
 THENCE SOUTH 02°02'23" WEST A DISTANCE OF 831.76 FEET TO A MAG NAIL (PS 1664) IN HILLTOP ROAD ON THE SOUTH LINE OF SAID SW1/4, SE1/4, OF SECTION 9;
 THENCE ALONG SAID SOUTH LINE NORTH 88°38'36" WEST A DISTANCE OF 450.35 FEET TO THE POINT OF BEGINNING, CONTAINING 373,505.14 SQUARE FEET, OR 8.58 ACRES, MORE OR LESS.

FLOOD ZONE INFORMATION
 NO PORTION OF THE PROPERTY DESCRIBED HEREON LIES WITHIN A SPECIAL FLOOD HAZARD AREA, ACCORDING TO THE FEMA FLOOD INSURANCE RATE MAP LISTED BELOW:
 PANEL # 05125C0325E, DATED: 06/05/2020

PROPERTY DESCRIPTION FROM SURVEY
 TRACT 2
 A PART OF THE SOUTHWEST QUARTER OF THE SOUTHEAST QUARTER (SW1/4, SE1/4) AND THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER (SE1/4, SE1/4) OF SECTION 9, TOWNSHIP 5 SOUTH, RANGE 14 WEST, SALINE COUNTY, ARKANSAS, MORE PARTICULARLY DESCRIBED AS FOLLOWS:
 COMMENCING AT A 2-1/2" ALUMINUM MONUMENT MARKING THE SOUTHWEST CORNER OF SAID SW1/4, SE1/4, OF SECTION 9;
 THENCE NORTH 07°49'03" EAST ALONG THE WEST LINE THEREOF A DISTANCE OF 821.57 FEET TO POINT;
 THENCE LEAVING SAID WEST LINE NORTH 89°44'37" EAST A DISTANCE OF 453.83 FEET TO A FND. 5/8" REBAR & CAP (PS 1506) AND THE POINT OF BEGINNING;
 THENCE SOUTH 02°02'23" WEST A DISTANCE OF 831.76 FEET TO A FND. 1/2" REBAR;
 THENCE NORTH 89°41'07" EAST A DISTANCE OF 126.28 FEET TO A FND. 1/2" REBAR;
 THENCE SOUTH 07°17'14" EAST A DISTANCE OF 100.11 FEET TO A FND. 1/2" REBAR;
 THENCE SOUTH 89°42'44" EAST A DISTANCE OF 100.02 FEET TO A FND. 1/2" REBAR;
 THENCE NORTH 07°08'50" WEST A DISTANCE OF 100.03 FEET TO A FND. 1/2" REBAR;
 THENCE NORTH 89°39'55" EAST A DISTANCE OF 635.46 FEET TO A FND. 1/2" PIPE AND THE NORTHWEST CORNER OF SAID, SE1/4, SE1/4, OF SECTION 9 ON THE WEST LINE OF LOMBARD HEIGHTS SUBDIVISION, PHASE 2, AS FILED FOR RECORD AS INSTRUMENT 2023-09236;
 THENCE ALONG SAID WEST LINE SOUTH 07°35'03" WEST A DISTANCE OF 63.20 FEET TO A FND. 5/8" REBAR AND THE SOUTHWEST-MOST CORNER OF LOT 40 OF SAID LOMBARD HEIGHTS, PHASE 2;

TO A FND. 5/8" REBAR AND THE SOUTHWEST-MOST CORNER OF LOT 40 OF SAID LOMBARD HEIGHTS, PHASE 2;
 THENCE ALONG THE SOUTH LINE OF SAID LOMBARD HEIGHTS, PHASE 2, SOUTH 88°39'36" EAST A DISTANCE OF 869.49 FEET TO A SET 1/2" REBAR & CAP (PS 1664) ON THE SOUTH LINE OF LOT 30 OF SAID LOMBARD HEIGHTS, PHASE 2;
 THENCE SOUTH 70°39'54" EAST A DISTANCE OF 55.24 FEET TO A SET 1/2" REBAR & CAP (PS 1664) AT THE SOUTHWEST CORNER OF LOT 30 OF SAID LOMBARD HEIGHTS, PHASE 2;
 THENCE ALONG THE SOUTH LINE OF SAID LOT 30 SOUTH 89°33'49" EAST A DISTANCE OF 120.02 FEET TO THE SOUTHEAST CORNER THEREOF;
 THENCE LEAVING SAID SOUTH LINE SOUTH 07°42'20" WEST A DISTANCE OF 568.8 FEET TO A 5/8" REBAR & CAP (PS 568);
 THENCE NORTH 88°37'35" WEST A DISTANCE OF 467.02 FEET TO A FND. 5/8" REBAR & CAP (PS 568);
 THENCE NORTH 88°52'07" WEST A DISTANCE OF 467.71 FEET TO A FND. 5/8" REBAR & CAP (PS 568);
 THENCE NORTH 88°59'03" WEST A DISTANCE OF 329.43 FEET TO A FND. 5/8" REBAR;
 THENCE SOUTH 02°17'06" WEST A DISTANCE OF 660.32 FEET TO A SET 1/2" REBAR & CAP (PS 1664) ON THE SOUTH LINE OF SAID SE1/4, SE1/4, OF SECTION 9;
 THENCE ALONG SAID SOUTH LINE NORTH 88°38'36" WEST A DISTANCE OF 1,236.57 FEET TO A MAG NAIL (PS 1664) IN HILLTOP ROAD;
 THENCE LEAVING SAID SOUTH LINE NORTH 88°38'36" EAST A DISTANCE OF 831.76 FEET TO THE POINT OF BEGINNING, CONTAINING 1,973,470.21 SQUARE FEET, OR 45.30 ACRES, MORE OR LESS.

RECORD PROPERTY DESCRIPTION
 A PORTION OF SALINE COUNTY INSTRUMENT DEED 2020-008135

REFERENCE DOCUMENTS CITED
 RECORDED SURVEY PLATS BY:
 RASBERRY (PS 1506), DATED 8-14-200, FOR THOMPSON SHAMBERGER (PS 1508), DATED 6-2-2007, FOR JONES

SURVEY DETAILS AND NOTES
 OWNER OF RECORD: NXT GEN HOMES, LLC
 PHYSICAL ADDRESS: HILLTOP RD AND MILLER RD
 COUNTY PARCEL TAX ID: PART OF 840-1625-025
 CURRENT ZONING: R-2 RESIDENTIAL DISTRICT

ALL DIMENSIONS LISTED ARE AS MEASURED BY THIS SURVEYOR UNLESS OTHERWISE NOTED. FOR RECORD DIMENSIONS SEE DOCUMENTS OF RECORD.

OWNERSHIP INFORMATION, IF SHOWN, IS LISTED AS PUBLISHED BY THE LOCAL COUNTY TAX ASSESSOR AND IS LISTED FOR REFERENCE ONLY. NO STATEMENTS OF OWNERSHIP, RIGHTS, OR INTERESTS ARE MADE.

THIS SURVEY IS BASED ON PUBLIC RECORDS AND/OR TITLE INVESTIGATIONS FURNISHED BY THIRD PARTIES. NO INDEPENDENT SEARCH OR INVESTIGATION HAS BEEN MADE BY THIS FIRM FOR ANY RECORDS, PUBLIC OR PRIVATE, LISTED REFERENCE DOCUMENTS HEREON WERE USED AND CONSIDERED AS A PART OF THIS SURVEY; HOWEVER OTHER RECORDS, IF ANY, COULD FURTHER AFFECT THIS SURVEY. NO STATEMENT OR GUARANTEES OF OWNERSHIP, RIGHTS, OR OTHER INTERESTS ARE MADE BY THIS SURVEY PLAT.

TYPICAL LOT SETBACKS:
 FRONT: 25 FEET
 SIDE (EXTERIOR): 15 FEET
 SIDE: 8 FEET
 REAR: 25 FEET

TYPICAL UTILITY & DRAINAGE EASEMENTS:
 FRONT: 5 FEET
 SIDE: 5 FEET
 REAR: 5 FEET

LEGEND

- - PLSS Aliquot Corner
- - Fnd. Corner Monument
- △ - Computed Point
- (M) - As Measured
- (P) - Per Deed or Plat Records
- ESMT - Easement
- B.S.L. - Building Setback Lines
- Clean Out
- Water Meter
- Power Pole
- Sewer Manhole
- Light Pole
- Telephone Pedestal
- Drainage Manhole
- Gas Meter
- Fence
- Overhead Power
- Sewer Line
- Water Line
- Telephone Line
- Electric Line
- Gas Line

SCALE: 1" = 100'

HOPE CONSULTING ENGINEERS - SURVEYORS
 129 North Main Street
 Benton, Arkansas 72015
 Office: (501) 315-2626 | Fax: (501) 315-0024
 www.HopeConsulting.com

TRACT SPLIT
 PART OF THE SE 1/4, SE1/4 & PART OF THE SW1/4, SE 1/4, SECTION 9, TOWNSHIP 5, RANGE 14 W, SALINE COUNTY, ARKANSAS

FOR USE AND BENEFIT OF:
 NXT GEN HOMES, LLC

CORNER OF HILLTOP RD & MILLER RD
 ALEXANDER, ARKANSAS, 72002

DATE: 06/20/2024
 REVISIONS: 1 OF 1
 SHEET: 1 OF 1

CAD BY: CV
 CHECKED BY:
 SCALE: 1" = 100'

PROJECT NUMBER:
24-0752

AR STATE LAND SURVEY FILING CODE: 500 - 01S - 14W - 0 - 09 - 200 - 62 - 1664